

**BID NUMBER #05-24  
SHAKER ROAD AND TWIN BRIDGE ROAD  
DRAINAGE PROJECT  
CONTRACTOR'S PROPOSAL**

To: Town of Northfield NH:

The undersigned, as a lawfully authorized agent for the below named Bidder/Contractor, has carefully examined the Proposal form of this Bid, to be known as Bid Number #05-24 Shaker Road and Twin Bridge Drainage Project, with the General Provisions, Specifications and other bid documents and binds himself/herself and his/her company on award to them by the Board of Selectmen to execute a contract agreement under this Proposal in accordance with such award, on such form and in such manner as is prescribed by the Town and to provide all necessary equipment, labor, materials and other items or services needed to perform all the requirements for the project Drainage Project, Northfield, NH for the following:

**COST OF WORK PERFORMED ON SHAKER RD DRAINAGE PROJECT**                      \$ 204,613.00

**COST OF WORK PERFORMED ON TWIN BRIDGE RD DRAINAGE PROJECT**                      \$ 227,113.00

**TOTAL COST \$** 431,726.00 (must include any mobilization fees)

I acknowledge that I have read and understand the instructions and specifications of the proposed agreement, minimum specifications, and this bid sheet.


Respectively submitted,

BRANDON HILTZ CONSTRUCTION INC.

Print Bidder/Contractor's Name

BRANDON HILTZ

Print Representative's Name and Title



04/19/2024

Representative's Signature

Date

PO BOX 43

ASHLAND

NH

03217

Street

City

State

Zip

603-557-9095

Telephone

Fax Number

BRANDON@BRANDONHILTZCONSTRUCTIONINC.COM

Email

Person signing proposal must be a person in your company authorized to sign a Contract with the Town of Northfield, NH.

## SHAKER ROAD AND TWIN BRIDGE ROAD SCOPE OF WORK

The Scope of Work shall include: Installing Under drain in shoulder of roadway, replace cross culverts, replace driveway culverts, shape and stone line swales, improve shoulders, install catch basins, drop inlets, grates and frames. Engineering provided and plans to be followed.

Date the road is available: ..... June 1, 2024 (maybe earlier depending on mud season)

Date of completion: ..... October 1, 2024

Start Location:	Intersection of Shaker Rd & Twin Bridge Rd
End Location:	Intersection of Knowles Pond Rd & South Rd
Length (estimated):	4300 ft
Width (estimated):	21 ft
Traffic Control:	Yes

	Est. Quantity	Unit		
Clean & Shape Swale:	1500	Ft		
Excavate Waste	3200	Cubic Yards		
Class C Stone	1200	Cubic Yards		
Hydroseeding	5900	Square Feet		
1 1/2" Washed Crushed Stone	2140	Cubic Yards		
Gravel (NHDOT 304.3)	150	Cubic Yards		
Pavement Patch 2" Binder	40	Ton	\$ 200	Per Ton

Materials Supplied by the Town, installed by Contractor	Est. Quantity	Unit
Catch Basins & Grates	9	CB
15" Under Drain	4600	Ft
18" Under Drain	240	Ft
Cross Culverts / Driveway Culverts	120	Ft
Filter Fabric	10,200	Sq Yards
Erosion Control Matting	720	Sq Yards